

## LAR-IAC2

### Dewberry Status for Independent QA/QC

July 24, 2008

Slides provided by  
Dave Maune, PhD, PSM, PS, GS, CP, CFM  
Project Manager  
Dewberry & Davis



## Dewberry QA/QC & Production Tasks

- QA/QC Project Management
- QA/QC of Aerial Triangulation Reports
- QA/QC of Urban Area 4" Orthophotos
- QA/QC of National Forest 1' Orthophotos
- QA/QC of Breakline/DTM Spot Updates
- QA/QC of Oblique Aerial Digital Images
- Full Delivery, County & SLDS
- Additional Data Products
- Mosaic Generation



## QA/QC Project Management

- Developed and coordinated the LAR-IAC2 Quality Plan, version 2
- Continued to review Pictometry's procedures for Aerial Triangulation (AT) of "superblocks" to ensure that orthophotos do not have excessive seamline issues from the many thousands of small images that comprise the LAR-IAC2 datasets.



"Superblock" South-1 replaced 1A, 1B, 1C, 2A, 2B, 2C; still has seams issues with next block to north

